

Scaling Up Passivhaus

THE CENTRE FOR MEDICINE, UNIVERSITY OF LEICESTER

Predicted Performance

Specific building demands with reference to the treated floor area

	Treated floor area	9655.0 m ²	Requirements	Fulfilled?*
Space heating	Heating demand	12.11 kWh/(m ² a)	15 kWh/(m ² a)	yes
	Heating load	10 W/m ²	10 W/m ²	yes
	Overall specif. space cooling demand	kWh/(m ² a)	15 kWh/(m ² a)	yes
Space cooling	Cooling load	W/m ²	-	-
	Frequency of overheating (> 25 °C)	%	-	-
Primary energy	Heating, cooling, auxiliary electricity, dehumidification, DHW, lighting, electrical appliances	119 kWh/(m ² a)	120 kWh/(m ² a)	yes
	DHW, space heating and auxiliary electricity	54 kWh/(m ² a)	-	-
	Specific primary energy reduction through solar electricity	kWh/(m ² a)	-	-
	Airtightness	Pressurization test result n ₅₀	0.3 1/h	0.6 1/h

* empty field: data missing; -: no requirement

U-values: Walls 0.13W/m²/k
 Roof 0.13W/m²/k
 Floor 0.13W/m²/k



Airtightness: 1m³/m²/hr @ 50Pa

Equates to: 0.33 ac/h

Treated floor area: 9,655 m²

Annual Heat balance kWh/m²

	Losses	Gains
Windows	19.8	
Roof	2.7	
Floor	2.6	
Wall	3.9	
Other	0.2	
	0.0	
Thermal Brid	2.1	
Infiltration	2.3	
Ventilation	5.6	
Solar		11.4
Internal		14.9
Heating		13.0
Totals	39.3	39.3




Turn off htg display? No

Window breakdown

	Losses kWh/m ²	Heat gains kWh/m ²	Balance kWh/m ²	area m ² (% of wall)
North	2.8	1.0	-1.8	715.5 (8.7%)
East	6.7	4.1	-2.6	1,658.5 (20.2%)
South	2.9	2.2	-0.8	721.2 (8.8%)
West	6.2	2.4	-3.7	1,556.5 (19.0%)
Horizontal	1.3	2.4	1.1	232.4 (2.8%)
Total	19.8	12.1	-7.8	4,651.7 (56.7%)

Heat loss form factor (what is it?)

Heat loss form factor	
Wall	0.8
Roof	0.3
Floor	0.3
Other	0.0
Total	1.52



Average fabric U value required	0.277 W/m ² .yr
Average fabric U value of design	0.232 W/m ² .yr

Heat Losses

1 Windows	191,576 kWh/a
2 Exterior wall - Ambient	31,731 kWh/a
3 Roof/Ceiling - Ambient	26,395 kWh/a
4 Floor slab / Basement ceil	25,222 kWh/a
5 Exterior TB (length/m)	16,388 kWh/a

The Design Team



Client

BIDWELLS

Project Managers



Cost Consultants

AssociatedArchitects

Architect and Lead Consultant



M+E Engineers

Passivhaus Designers

RAMBOLL

Structural and Civil Engineers

Pre Contract

Post Contract

BIDWELLS

Project Managers



Cost Consultants

AssociatedArchitects

Design Advisor



Technical Advisor

Client's Retained Consultants



WILLMOTT DIXON

SINCE 1852

Main Contractor

Passivhaus Designers

AssociatedArchitects

Architect and Lead Consultant



M+E Subcontractor



Passivhaus Consultants

RAMBOLL

Structural and Civil Engineers

Contractor's Design Team

An Overview of the 2011 Client Brief:

- Bring together the Schools of Medicine, Health Sciences and Psychology
- Adjacent to the existing medical building
- Sensitive to context ñ ecology and heritage
- Contribute towards reducing the University’s carbon footprint ñ passive design
- Allow the existing building to be upgraded in the future
- 13,000sqm of teaching, research and support spaces for 2,400 occupants
- Range of flexible teaching spaces with potential for conference use
- Deliver the building by September 2015




Background Site Information – Regent College Site



Planning Issues


- ï Locally listed building (Regent College)
- ï 'Conservation Area' and listed 'Fire Station Cottages'
- ï Protected trees on site boundary
- ï Protected views towards the War Memorial
- ï Risk of overshadowing adjacent buildings
- ï Loss of open space & playing fields
- ï Ecological impact
- ï Concerns over car parking provision
- ï Bomb shelter & potential archaeology




Design Approach

- ï Demolish bomb shelter - provide new football pitch
- ï Increase site biodiversity
- ï Respect Regent College
- ï Face the University and mark the start of the campus
- ï Provide an efficient plan form
- ï Maximise passive measures


Concept ñ Plan Form




- 1.
- Square block responds to site boundaries.
 - Split block up allowing views through into site.
 - Narrow floor plate to max daylight.
 - Landscape planted through building gaps.
 - Stepped heights of blocks high to Uni Rd.



- 2.
- Rotate blocks to face directly south.
 - Orientation best to control solar gain.
 - Building faces the corner legible entrance!



- 3.
- Blocks turn back on College grid into site responding to context.
 - Rotation provides a pedestrian arrival space and separate service zone.




- 4.
- Prickly façade animates building protection from solar gain.

High Level View from the Roof of MSB



Proposed Site Layout





Contractor's Proposals – Environmental

**Full curtain walling with brick slip panels
(concrete backing panels for thermal mass)**

**Active external shading blinds
(continuous blind box detail as part
of curtain wall façade)**


**Highly insulated cavity wall
to lower floors**

Plant rooms brought inside Passivhaus 'TFA'


**Efficient AHUs with Heat Recovery
(distribution within ceiling voids of occupied floors only)**

**Changed to insulated
render**

**GAHE Labyrinth
(change to vent towers)**




Tender: Precast Concrete Sandwich Panel




- ï Unitised curtain walling windows between precast brick slip clad panels
- ï Air seals on all four sides
- ï Opening vent panel behind fixed louvre
- ï Individual blind box for each window
- ï Thermal mass

CPs: Full Curtain Walling with Brick Slips




- ï Full curtain walling façade ñ storey height screens
- ï Brick slip panels fixed to insulated metal panels
- ï Reduced requirements air seals
- ï Opening vent panel behind fixed louvre
- ï Continuous blind box around slab perimeter
- ï Thermal mass replaced by non-structural infill

Tender: Precast Concrete Sandwich Panel



CPs: Full Curtain Walling with Brick Slips





Pros:

- ï Single subcontractor responsibility
- ï Easier construction
- ï Faster programme
- ï Tighter tolerances

Tender: Precast Concrete Sandwich Panel

CPs: Full Curtain Walling with Brick Slips






Cons:

- ï Planning risk
- ï Additional movement joints
- ï Risk of interstitial condensation
- ï Additional seals / VCLs required
- ï Overall fa ade zone increased ~150mm
- ï Greater coordination with PT frame

External Shading Blinds

- ï CTB blinds - not used before in UK
- ï UoL nervousness about maintenance
- ï Automatic operation ñ linked to BMS
- ï Automatically retract in high winds
- ï Tender design - small sections
- ï Contract - continuous ribbon
- ï Blind box - thermal weak link



$$U_f = \frac{3.801}{30} = 0.128$$

$$0.495$$

$$U_f = 0.256 \text{ W/m}^2\text{K}$$

Certificate

Certified Passive House component for cool, temperate climate, valid until 31. 12.2013

Passive House Institute
Dr. Wolfgang Feist
84283 Darmstadt
GERMANY

Category: **Curtain Wall**
Manufacturer: **Schüco International KG**
33809 Bielefeld, GERMANY
Product name: **FW 50+ SI PH zert. (Alu Anpress.)**

The following comfort criteria were used in awarding this certificate:

Given a U_g value of 0,7 W/(m²K) and an element size of 1,23 m by 2,50 m,

$U_{CW} = 0,80 \text{ W/(m}^2\text{K)} \leq 0,80 \text{ W/(m}^2\text{K)}$

Taking into account the installation based thermal bridges, and provided that the installation is, with regard to the thermal bridges, equal or better than shown in the data sheet, the facade meets the following criteria:

$U_{CW,avg,best} \leq 0,85 \text{ W/(m}^2\text{K)}$

Thermal data of the construction


	U_f -value [W/(m ² K)]	Width [mm]	Ψ_{gl} [W/mK]	$f_{Rsi-HL2}$ [-]
Spacer				Beispacer V*
Transom (t)	0,64	50	0,036	0,82
Mullion (m)	0,85	50	0,036	
Thermal glass carrier bridge Ψ_{gl} [W/K]				0,014





*Spacers of lower thermal quality, especially those made of aluminium, lead to significantly higher thermal losses and lower temperature factors.


Further information see data sheet

www.passivehouse.com 0173zw95

CERTIFIED COMPONENT
Passive House Institute







Façade Mock-Up Panel





Thermal Envelope

Tender:

- Roof top plant rooms outside thermal envelope
- Basement plant room inside the thermal envelope


Contract:

- All plant rooms inside thermal envelope
- Increased Treated Floor Area
- Ventilation duct runs inside thermal envelope
- Simplification of scheme



Cold Duct Runs

- Extensive cold duct runs within envelope
- Plant room layouts changed to minimise cold duct runs
- Suitable AHUs not available as PH certified products



Thermal Bridging


- ï Minimising thermal bridging is crucial
- ï Couldn't all be eradicated or calculated prior to contract
- ï Schedule of thermal bridges compiled
- ï WDES did thermal modelling
- ï Pile caps insulated on all sides, piles not insulated
- ï Thermal pads included on all steelwork connections
- ï GRC cladding changed to insulated render

Thermal bridge description	Base 2A estimate		WD proposal	
	Ψ W/(mK)	% losses	Ψ W/(mK)	% losses
Balustrade/mansafe fixings	0.000		0.000	
Parapet wall	0.150	1.5%	0.100	1.5%
Plant room upstands for walls	0.200	0.7%	0.200	
Plantroom to internal space	0.000		0.000	
Rooflight upstands - will be insulated			0.200	
Wall-roof with balustrade	0.200	0.1%	0.100	0.0%
W 13 Inverted wall-roof junction	0.200	1.0%	0.048	0.3%
Rooflight-wall junction	0.300	0.6%	0.300	0.7%
Thresholds	0.200		0.200	
Wall-window junction	0.070		0.070	
shade support fixings				
structure (columns & floors) into walls	0.000		0.000	
W 14 Collonade soffit to wall beneath	0.050	0.1%	0.075	0.2%
Cladding support to collonade soffit & wall - e	0.100	0.7%	0.100	
Collonade CONC soffit to support column	4.000	1.9%	4.000	2.2%
Collonade STEEL soffit to support column	4.000	1.6%	0.650	0.3%
Windposts			0.000	
Ground pile caps in basement - various configur	1.500	0.8%	1.500	0.9%
Ground floor single piles in centre of floor	1.500	1.4%	1.500	1.4%
Ground floor single piles at perimeter	1.000	0.5%	0.770	0.2%
Perimeter ground beam	0.100	0.2%	0.000	
		10.9%		7.7%



Ground-Air Heat Exchanger

- Redesigned to ease construction
- GAHE located beneath the building
- Extensive coordination ñ design period increased
- Vent towers integrated into ãdummyí columns
- Verifying the efficiency of the system to suit PHI
- Very deep excavations
- Installation took longer than anticipated



08 September 2014



Conclusions

- On track - September 2015 and Passivhaus certification
- Difficulties sourcing products to suit the aesthetic
- Lack of Passivhaus knowledge and experience amongst contractors
- PHPP proved a useful design tool
- Effective communication of key design requirements - ?
- Site supervision - ?
- Increased capital costs for Passivhaus have fallen
- Achieving DEC A will be a challenge